ROOM FINISH - SCHEDULE WALL COVERS AND PAINT
ST. PETERSBURG CLEARWATER AIRPORT TERMINAL IMPROVEMENTS PROJECT PHASE 1 **4/2/2009**
KELLY TAAFFE DESIGN, INC.

		WALL FINISHES				SOFFIT	
ROOM#	FLOOR/BASE	NORTH	SOUTH	EAST	WEST	CLNG	REMARKS
PHASE C - GATES 2-6							**(*1) RCP FOR GATES 2-6 (A.1.11) FOR SOFFIT LOCATION**
CL 100	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 101	BY OTHERS	**WC-1**	**WC-1**	BY OTHERS	**WC-1**	P7(*1)	SEE I.1.02 FOR W.COV. PLACEMENT INCL STAIRWELL /"WALL PREP. BY OTHERS"
CL 102	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 103	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 104	BY OTHERS	N/A	N/A	N/A	N/A	N/A	R/# NOT ON FLOOR PLAN
CL 105	BY OTHERS	N/A	N/A	N/A	N/A	N/A	R/# NOT ON FLOOR PLAN
CL 106	BY OTHERS	N/A	N/A	N/A	N/A	N/A	R/# NOT ON FLOOR PLAN
CL 107	BY OTHERS	APPLY P-3 ALL FINISH GYP BOARD WALLS, SILLS, PARTIAL WALLS EXCEPT WHERE WALL COVER PREP IS DENOTED				P7(*1)	SEE I.1.02 FOR W.COV. PLACEMENT, **WALL PREP INCLUDED**
CL 108	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 110	BY OTHERS	NO FINISH	**WC-2**	**WC-2**	**WC-2**	P7(*1)	SEE I.1.02 FOR W.COV. PLACEMENT/ "WALL PREP. BY OTHERS"
CL 111	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 112	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 113	BY OTHERS	**WC-2**	**WC-2**	**WC-2**	**WC-2**	P7(*1)	SEE I.1.02 FOR W.COV. PLACEMENT/ "WALL PREP. BY OTHERS"
CL 115	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 116	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 117	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 118	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 119	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 120	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 121	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 122	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 123	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 124	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 125	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 126	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 127	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 127	BY OTHERS	BY OTHERS	BY OTHERS	**WC-1**	**WC-1**	P7(*1)	-
CL 128	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
CL 128	BY OTHERS	BY OTHERS	BY OTHERS	**WC-1**	**WC-1**	P7(*1)	-
CL 129	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	BY OTHERS	P7(*1)	-
PHASE B - TICKETING A							
TA 101	NO WORK	**WC-1**	**WC-1**	**WC-1**	**WC-1**	P7	SEE I.1.01 FOR W.COV. PLACEMENT. P-7@SOFFITS
TA 102	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 103	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 104	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 105	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 106	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 107	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 108	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 109	BY OTHERS	BY OTHERS	BY OTHERS	**SEE NORTH WALL**	**SEE NORTH WALL**	-	-
TA 109	BY OTHERS	**WC-1**	**WC-1**	BY OTHERS	BY OTHERS	-	-
TA 110	BY OTHERS	BY OTHERS	BY OTHERS	**SEE NORTH WALL**	**SEE NORTH WALL**	-	-
TA 110	BY OTHERS	**WC-1**	**WC-1**	BY OTHERS	BY OTHERS	-	-
TA 111	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
TA 112	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
PHASE D - TICKETING B							
TB 100	BY OTHERS	-	-	-	-	-	-
TB 101	BY OTHERS	WC-1	WC-1	WC-1	WC-1(ON RM TB119)	-	SEE I.1.04 FOR WALL COV. PALCEMENT
TB 102	BY OTHERS	-	-	WC-1	-	-	SEE I.1.04 FOR WALL COV. PALCEMENT
TB 103	N/A	N/A	N/A	N/A	N/A	-	R/# NOT ON FLOOR PLAN
TB 104	BY OTHERS	-	-	-	-	-	-
TB 105	BY OTHERS	-	-	-	-	-	-
TB 106	BY OTHERS	-	-	-	-	-	-
TB 107	BY OTHERS	-	-	-	-	-	-
TB 108	N/A	N/A	N/A	N/A	N/A	-	R/# NOT ON FLOOR PLAN
TB 109	BY OTHERS	-	-	-	-	-	-
TB 110	BY OTHERS	-	-	-	-	-	-
TB 111	BY OTHERS	-	-	-	-	-	-
TB 112	BY OTHERS	-	-	-	-	-	-
TB 113	BY OTHERS					-	
TB 114	N/A	N/A	N/A	N/A	N/A	-	R/# NOT ON FLOOR PLAN
TB 115	BY OTHERS	-	-	-	-	-	-
TB 116	BY OTHERS	-	-	-	-	-	-
TB 117	N/A	N/A	N/A	N/A	N/A	-	R/# NOT ON FLOOR PLAN
TB 118	BY OTHERS	-	-	-	-	-	-
TB 119	BY OTHERS	-	-	-	-	-	-

		WALL FINISHES					
ROOM#	FLOOR/BASE	NORTH	SOUTH	EAST	WEST		REMARKS
CUSTOMS INSPECTIONS							
FS 100	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 101	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 102	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 103	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 104	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 105	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 106	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 107	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 108	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 109	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 110	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 111	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 112	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 113	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 114	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 115	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 116	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 117	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 118	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 119	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 120	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 121	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 122	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 123	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 124	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 125	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 126	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 127	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
FS 128	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	-	-
PHASE A - GATES 9-12							**(*2) REF TO A1.1.05 FOR WC PLACEMENT @ RESTROOM ENTRY**
GB 100	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 101	BY OTHERS	**WC-1**	**WC-1**		-	**P7**	SEE I.1.05 FOR W.COV. PLACEMNET
GB 102	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK		
GB 103	BY OTHERS	**P3**	**P3**	**P3**	**P3**	**P7**	GLASS HALF WALL APPROX 4' TO RECEIVE PAINT
GB 104	BY OTHERS	-	-	-	-	-	-
GB 105	BY OTHERS	**P3**	**P3**	**P3**	**P3**	**P7**	GLASS HALF WALL APPROX 4' TO RECEIVE PAINT
GB105E	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 106	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 107	BY OTHERS	**P3**	**WC-1**	**P3**	-	-	GLASS HALF WALL APPROX 4' TO RECEIVE PAINT
GB 108	BY OTHERS	**P4**	**N/A**	**P4**	**WC-1**	**P7**	GLASS HALF WALL APPROX 4' TO RECEIVE PAINT
GB 109	BY OTHERS	**P6**	**P6**	**P6**	**P6**	**P7**	**(*2)** PAINT FROM TOP OF WALL TILE TO CLNG. REF TO I.4.01
GB 110	BY OTHERS	**P6**	**P6**	**P6**	**P6**	**P7**	**(*2)** PAINT FROM TOP OF WALL TILE TO CLNG. REF TO I.4.02
GB 111	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 112	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 113	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 114	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 115	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 116	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
PHASE B - BAGGAGE CLAIM							**(*3) INCLUDE SKYLIGHTS**
BC 100	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK		
BC 101	BY OTHERS	**WC-4**	**P3**	**P3**		P7(*3)	SEE SHEET I.1.06 FOR W.COV. PLACEMENT
BC 102	BY OTHERS	**P6**	**P6**	**P6**	**P6**	P7(*3)	-
BC 103	BY OTHERS	-	-	-	-	P7(*3)	-
BC 104	BY OTHERS	**P6**	**P6**	**P6**	**P6**	P7(*3)	-
BC 105	BY OTHERS	-	-	-	-	P7(*3)	-
BC 106	BY OTHERS	**P6**	**P6**	**P6**	**P6**	P7(*3)	-
BC 107	BY OTHERS	-	-	-	-	P7(*3)	-
BC 108	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 109	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 110	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 111	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
GB 111	N/A	N/A	N/A	N/A	N/A	-	R/# ON ARCH. BACKGROUND SHOULD READ BC 111, SEE ROW ABOVE
BC 112	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 113	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 114	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 115	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
BC 116	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-

		WALL FINISHES					
ROOM#	FLOOR/BASE	NORTH	SOUTH	EAST	WEST		REMARKS
LEVEL II RESTAURANT							
CL 200	BY OTHERS	**WC-03**	**WC-03**	**WC-03**	**WC-03**	**P7**	SEE 1.02 FOR 1ST LEVEL WALL COVER,**STAIRWELL=WC-01**
CL 201	BY OTHERS	**WC-03**	**WC-03**	**WC-03**	**WC-03**	**P7**	SEE I.1.07 FOR HALF AND FULL COVER WALL PLACEMENT
CL 202	BY OTHERS	**WC-03**	**WC-03**	**WC-03**	**WC-03**	**P7**	SEE I.1.07 FOR W.COV. PLACEMENT
CL 203	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
CL 204	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
CL 205	BY OTHERS	-	**WC-03**	**WC-03**	**WC-03**	**P7**	-
CL 206	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
CL 207	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
CL 208	BY OTHERS	NO WORK	NO WORK	NO WORK	NO WORK	-	-
CL 209	BY OTHERS	**WC-03**	**WC-03**	**WC-03**	**WC-03**	**P7**	SEE I.1.07 FOR HALF AND FULL W.COVER WALL PLACEMENT
CL 210	BY OTHERS	**WC-03**	**WC-03**	**WC-03**	**WC-03**	**P7**	-

* ALL CEILINNGS + SOFFITS IN LEVEL2 RESTAURANT ALSO INCLUDED

GENERAL NOTE:

ALL TRIM (CASINGS, DOOR FRAMES, ETC.), WALLS AND DOORS RECEIVING FRESH PAINT ***IN THIS CONTRACT*** MUST MATCH NEWLY PAINTED TRIM, DOORS, AND WALLS THAT HAVE RECENTLY BEEN PAINTED "BY OTHERS" IN TICKETING B AND GATES 2-6 AREAS!!! CONTRACTOR FOR THIS PROJECT RESPONSIBLE FOR MAKING SURE OF THIS MATCH.

WORK SCOPE FOR THIS CONTRACT INCLUDES ***SOFFITS AND CEILINGS AS-NEEDED*** (MUCH OF THE CEILING AREAS CONSIST OF ACOUSTICAL TILE WITH SOFFITS AT THE PERIMETER. (**MANDATORY WALK-THROUGH**). SOFFITS AND CEILINGS TO RECEIVE P-7, 1 TO 2 COATS AS NEEDED TO GIVE SMOOTH FULL COVERAGE OF ALL SURFACES

THE MAJORITY OF THE PROJECT WILL REQUIRE 2 COATS OF PAINT (NOT INCLUDING PREP AND PRIMERS), BAG CLAIM MAY BE THE EXCEPTION WHERE EXISTING PAINT COLOR SIMILAR TO NEW. IN THE END, THE PAINT CONTRACTOR IS RESPONSIBLE FOR PROVIDING COMPLETE COVERAGE WITHOUT STREAKING OR SHADING. MINOR IMPERFECTIONS MUST BE PATCHED AND PAINTED SO AS TO BE UNDETECTABLE.

AREA CL107 AND ADJOINING RESTROOMS #CL127 AND #CL128 WILL NOT BE READY FOR PAINTING AND WALL COVERING UNTIL MID-YEAR 2010.

FOR THE PAINT AND WALL COVERING PROJECTS, COORDINATION WITH EXISTING ON-SITE GENERAL CONTRACTOR, AND AIRPORT OPERATIONS STAFF WILL BE REQUIRED .

ALL INTERESTED CONTRACTORS MUST ATTEND THE **MANDATORY WALK THROUGH** PRIOR TO SUBMITTING YOUR PROPOSAL. FAILURE TO ATTEND WILL **DISQUALIFY** YOUR PROPOSAL

IT IS ASSUMED THE WORK OF THIS PROJECT WILL BE PERFORMED DURING REGULAR WORKING HOURS. 6'-0" HIGH BARRICADES MUST BE UTILIZED AT ALL TIMES.

CONTRACTOR TO REMOVE ANY EXISTING WALL COVER, REPAIR AND PREP WALLS AND REINSTALL NEW WALL COVER IN AREAS AS NOTED ON SCHEDULES AND DRAWINGS.

IMPORTANT: WALL FINISHES FOR PERIMETER WALKWAY NOT ON THIS SCHEDULE! SEE SHEETS WI.1.01/WI1.04/WI.1.05/WI.0.00 FOR WALL FINISHES IN THE THE PERIMETER WALKWAY.

REFERENCE SHEETS I.1.01/I.1.02/I.1.04/I.1.05/I.1.07/I.4.01/I.1.6.02/ A.1.11/A.1.15 FOR WALL COVER AND PAINT ONLY.

NOTE:

PAINTING TRIM ABUTTING THE WALL COVERING BY CONTRACTOR,IT IS THE RESPONSIBILITY OF THE CONTRACTOR, TO COORDINATE W/ THE WALL COVERING SUCH THAT ALL TRIM SURFACES RECEIVING PAINT ABUTTING WALL COVERING BE PAINTED PRIOR TO WALL COVER INSTALL.

CONTRACTOR TO REMOVE ANY EXISTING WALL COVER, + SKIM WALLS IN ALL PUBLIC AREAS OF TERMINAL LEVEL ONE AND RESTAURANT LEVEL 2 (INCL. STAIRWELL, SEE NOTE ON I.1.02 / RM CL101) CONTRACTROR TO INSTALL NEW WALL COVER IN AREAS TICKETING B.
WALL PREP. IS "BY OTHERS", ALL OTHER AREAS RECEIVING WALL COV. TO BE PRIMED BY CONTRACTOR. SEE FINISH SCHEDULE FOR LOCATIONS WHERE WALL COVER WALL PREP. PROVIDED BY OTHERS.

"THE PAINTED SURFACES IN THE REFLECTED CEILING PLANS ARE A PART OF THE CONTRACTOR'S SCOPE, SEE SHEET A111, A116 AND FINISH SCHEDULE FOR AREAS.

CONTRACTOR IS RESPONSIBLE FOR ALL THE TRIM PAINT IN THE FOLLOWING AREAS: BAGGE CLAIM, GATES 9-12, GATES9-12 RESTROOMS, TICKETING A, AND LEVEL 2RESTAURANT, AS WELL AS ROOM CL107 IN GATES 2-6 (SEE FINISH SCHEDULE).

ROOM FINISH SPECIFICATIONS

FLOORING, BY OTHERS N.I.C.

TZ-1	=	TERAZZO -EPOXY RESIN (SEE SHEET I4.01 & SPECBBOOK FOR DETAILS)	(BY OTHERS N.I.C.)
TZ-2	=	PRE-CAST DECO INSET-BROWN-SEE SPEC BOOK & SHEET I4.01 FOR DETAILS	(BY OTHERS N.I.C.)
TZ-3	=	PRE-CAST DECO INSET-GREEN-SEE SPEC BOOK & SHEET I4.01 FOR DETAILS	(BY OTHERS N.I.C.)
T-1	=	**PORCELAIN TILE- REFER TO PLAN SET & SPEC FOR TILE SPECIFICATION**	
C-1	=	MAIN CARPET, 3 FRAME WILTON WOVEN, 60 oz, 72'x 72'REPEAT	(BY OTHERS N.I.C.)
C-2	=	ACCENT CARPET, 3 FRAME WILTON WOVEN, 60 oz, 72'x 72',NO REPEAT	(BY OTHERS N.I.C.)
C-3	=	TUFTED, NEGLIGIBLE REPEAT, SEE WRITTEN TECHNICAL SPECS	(BY OTHERS N.I.C.)
C-4	=	WALK-OFFS TUFTED CARPET TILES	(BY OTHERS N.I.C.)
C-5	=	WALK-OFFS # BAG CL, MATCH EXISTING SYTSTEM, SEE WRITTEN TECHNICAL SPECS,	(BY OTHERS N.I.C.)
VCT	=	VINYL COMPOSITE TILE; ARMSTRONG; "EXCELON" COLOR DUTCH DELFT, OR APPROVED EQUAL	(BY OTHERS N.I.C.)

BASE, BY OTHERS N.I.C.

VB-1	=	VINYL COVE BASE-4" - JOHNSONITE: 4.00"X.125";COLOR: CHARCOAL OR APPROVED EQUAL	(BY OTHERS N.I.C.)
CB-1	=	CARPET BASE W/SURGED TOP-6"-	(BY OTHERS N.I.C.)
TB-1	=	**PORCELAIN TILE BASE - REFER TO PLAN SET & SPEC FOR TILE SPECIFICATION**	
TZB-1	=	6" PRE CAST TERAZZO BASE - STRAIGHT- DETAILS IN SPEC BOOK	(BY OTHERS N.I.C.)

PAINT:

SHERWIN WILLIAMS "SUPER PAINT"; "200 LINE"-MATCH **BENJAMIN MOORE(BM) COLORS IN SHERWIN WILLIAMS PAINTS,**
NEW PAINTS MUST MATCH NEW PAINTS IN ADJACENT PROJECTS

P-1	=	LATEX ENAMEL-METAL PAINT @ HOLLOW METAL DOORS-(INTERIOR)= SATIN FINISH , BM. #1038 EVERLASTING
P-2	=	LATEX ENAMEL-METAL PAINT@HOLLOW METAL DOOR CASINGS(INTERIOR)=SATIN FINISH, BM.#1044 LIGHTHOUSE LANDING
P-3	=	LATEX ACRYLIC - SCRUBBABLE: SATIN FINISH; BM. # 1038 EVERLASTING- SHERWIN WILLIAMS PROMAR200 ES
P-4	=	LATEX ACRYLIC - SCRUBBABLE: SATIN FINISH; COLOR SHERWIN WILLIAMS SW6142 MACADAMIA,SHERWIN WILLIAMS PROMAR 200 ES
P-5	=	LATEX ENAMEL METAL PAINT FOR HANDRAILS-COLOR SHERWIN WILLIAMS SW 6108 "LATTE".
P-6	=	LATEX ACRYLIC - SCRUBBABLE - SEMIGLOSS ,BM. # 1038 EVERLASTING
P-7	=	LATEX ACRYLIC, FLAT FINISH, COLOR=SHERWIN WILLIAMS SW# 7008 "ALABASTER", FLAT, SHERWIN WILLIAMS PROMAR 200
P-8	=	LATEX ENAMEL, SCRUBBABLE, SATIN FINISH, COLOR=BENJ.MOORE #1044 "LIGHTHOUSE LANDING"."USE AS NEEDED ON ANY WOOD TRIM THAT IS CURRENTLY PAINTED IN THE AREAS INCLUDED IN THE SCOPE OF THIS PROJECT(MAJORITY IN RESTAURANT LEVEL 2). **NOTE: CONTRACTOR TO REFINISH THE OAK STAINED WOOD BASE IN THE RESTAURANT ALONG THE FOODLINE ONLY. MATCH WAINSCOTT.**

SEAL WITH WATER RESISTANT SCRUBBABLE SEALANT

RESTROOMS GATES 9-12
CEILING SPEC.

WALL COVERING, SEE WALL COVER PLANS & FINISH SCHEDULE

* WALL COVER PRIMER SHERWIN WILLIAM

MAIN TERMINAL
GATES 2-6 CONCESSION
LEVEL II RESTAURANT
BAGGAGE CLAIM
LEVEL II RESTAURANT

WC-1	=	54" VINYL, SEE TECHNICAL SPECIFICATION FOR ORDERING INFORMATION- WOLF GORDON-YUTAKAWHITE GOLD, YUT7 -4024-54"W
WC-2	=	54" VINYL, SEE TECHNICAL SPECIFICATION FOR ORDERING INFORMATION-WOLF GORDON "EVORA – SAILCLOTH", EVO 5-1559
WC-3	=	54" VINYL, SEE TECH. SPEC. FOR ORDERING INFO.-WOLF GORDON "CARIBE- STRAW", CBE 5-1123(ALL BUT BACK WALL BEHIND SERVICE COUNTER, SEE WC-5)
WC-4	=	54" VINYL, SEE TECHNICAL SPECIFICATION FOR ORDERING INFORMATION-WOLF GORDON "EVORA – BLANCO-EVO 5-1565
WC-5	=	54" VINYL, (LEV.2 RESTAURANT WALL BEHIND SERVICE COUNTERS ONLY) SEE TECH. SPEC. FOR ORDERING INFORMATION-WOLF GORDON "EVORA-COFFEE", EVO 5-1557

WALL TILE @ RESTROOMS, BY OTHERS N.I.C.

T-1	=	PORCELAIN TILE: CROSSVILLE EMPIRE 28"X14" VS77/P0, PARISIAN WHITE PO ,OR APPROVED EQUAL	(BY OTHERS N.I.C.)
T-2	=	PORCELAIN TILE: CROSSVILLE EMPIRE 14"X14" VS77/P0, PARISIAN WHITE PO, OR APPROVED EQUAL	(BY OTHERS N.I.C.)
T-3	=	PORCELAIN TILE: CROSSVILLE EMPIRE 7"X7" VS77/P0, PARISIAN WHITE PO, OR APPROVED EQUAL	(BY OTHERS N.I.C.)
T-4	=	GLASSTILE: CROSSVILLE WATER CRYSTAL MOSAICS 1"X1" SUNSPRAY(BROWN),#WC020.101013 OR APPROVED EQUAL	(BY OTHERS N.I.C.)
T-5	=	GLASSTILE: CROSSVILLE WATER CRYSTAL LISTELLO 7/8"X8" EBBTIDE, SEASPARAY(OLIVE) IRRIDESCENT,#060, OR APPROVED EQUAL	(BY OTHERS N.I.C.)

St. Petersburg Clearwater International Airport

THE LPA GROUP
ENGINEERS ARCHITECTS PLANNERS
700 HUGER STREET
COLUMBIA, SOUTH CAROLINA 29201
POST OFFICE BOX 5805
COLUMBIA, SOUTH CAROLINA 29250-5805
Phone: 803/254-2211 Fax: 803/779-0482
DENNIS J. WIEHL FLORIDA ARCHITECT LICENSE # 11995
LPA GROUP INCORPORATED FLORIDA LICENSEE # AA0003054

KTD Inc. Design
KELLY TAAFFE DESIGN
Lic# ID 0002288
FL# 0015146
Kelly@Kellytaaffedesign.com
Tel.: 813.695.5049
Fax: 813.805.2371

KEY PLAN



REVISIONS

No.	Description	Date	By
01	ADDENDUM 1	04/20/09	KTD

Designed by:	Drawn by:	Checked by:

Project Name:

TERMIAL IMPROVEMENT PROJECT
WALL COVER & PAINT

Drawing Name:

FINISHES SCHEDULES

LPA Project Number:	FAA AIP Project Number:
AR178005.8	
Date: 04 / 20/ 2009	Division :

Drawing Number: FP-ALL.dwg

I.6.02

TERMINAL IMPROVEMENT PROJECT - WALL FINISHES