ROOM FINISH SCHEDULE
ST. PETERSBURG CLEARWATER AIRPORT TERMINAL IMPROVEMENTS PROJECT PHASE 1 **9/27/2007**
KELLY TAAFFE DESIGN, INC.

ROOM#	FLOOR/BASE	WALL FINISHES NORTH	SOUTH	EAST	WEST	REMARKS
CL 100	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	
CL 101	T-1, TB-1	P-3	WC-1	P-3/WC-1	WC-1	SEE I.1.02 FOR W.COV. PLACEMENT
CL 102	C1; CB-1	N/A	P-3	P-3	P-3	
CL 103	C1; CB-1	P-4	P-4	P-4	P-4	
CL 104	C1; CB-1	P-4	P-4	P-4	P-4	
CL 105	C1; CB-1	P-4	P-4	P-4	P-4	
CL 106	C1; CB-1	P-4	P-4	P-4	P-4	
CL 107	C1; CB-1					
CL 108	C1; CB-1	P-3	P-3	P-3	P-3	
CL 109	VCT;VB	P-3	P-3	P-3	P-3	
CL 110	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
CL 111	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
CL 112	NO FLOOR FINISH	P-5/P-6	P-5/P-6	P-5/P-6	P-5/P-6	P-6=WALLS/P-5=RAILS
CL 113	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
CL 114	C1; CB-1	P-3	P-3	P-3	P-3	
CL 115	VCT; VB-1	P-4	P-4	P-4	P-4	
CL 116	T-1;TB-1	P-3	P-3	P-3	P-3	
CL 117	T-1;TB-2	P-3	P-3	P-3	P-3	
CL 118	VCT;VB-1	P-4	P-4	P-4	P-4	
CL 119	VCT;VB-2	P-4	P-4	P-4	P-4	
CL 120	T-1, TB-1	P-3	P-3	P-3	P-3	
CL 121	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	
CL 122	NO FINISH	P-4	P-4	P-4	P-4	
CL 123	NO FINISH	P-4	P-4	P-4	P-4	
CL 124	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	
CL 126	NO WORK	NO WORK	NO WORK	NO WORK	NO WORK	
CL 127	TZ-1;TZB	T-1;THRU;T-5	T-1;THRU;T-5	T-1;THRU;T-5	WALL TILE ON W. WING WALL @ SINK	RESTROOMS // SEE SHEET I.4.01; PAINT ABOVE WALL TILE- COLOR TBD
CL 127	TZ-1;TZB	CONTINUATION OF RESTROOM TILE WALLS		WC-1	WC-1	VESTIBULES
CL 128	TZ-1;TZB	T-1;THRU;T-5	T-1;THRU;T-5	T-1;THRU;T-5	WALL TILE ON W. WING WALL @ SINK	RESTROOMS // SEE SHEET I.4.01; PAINT ABOVE WALL TILE- COLOR TBD
CL 128	TZ-1;TZB	CONTINUATION OF RESTROOM TILE WALLS		WC-1	WC-1	VESTIBULES
TA 10	TZ-1;TZB	T-1;THRU;T-5	SAME AS N.WALL@SINK WING WALL	SEE NORTH WALL	SEE NORTH WALL	SEE SHEET I.4.01
TA 10	TZ-1;TZ-2;TZ-3;TZB	WC-1	WC-1	CONTINUATION OF RESTROOM TILE WALLS		VESTIBULES// SEE SHEET I.4.01DETAILS
TA 110	TZ-1;TZB	T-1;THRU;T-5	SAME AS N.WALL@SINK WING WALL	SEE NORTH WALL	SEE NORTH WALL	SEE SHEET I.4.01
TA 110	TZ-1;TZ-2;TZ-3;TZB	WC-1	WC-1	CONTINUATION OF RESTROOM TILE WALLS		VESTIBULES// SEE SHEET I.4.01DETAILS
TB 100						NO WORK
TB 101	T-1;TB-1 REF I.104(*1)	P-3	WC-1	WC-1	WC-1	
TB 102	VCT-1/VB-1					
TB 103	C1; CB-1					
TB 104	C1; CB-1					
TB 105	VCT-1/VB-1	P-4	P-4	P-4	P-4	
TB 106	NO FINISH	P-4	P-4	P-4	P-4	
TB 107	NO FINISH	P-4	P-4	P-4	P-4	
TB 108	NO FINISH					
TB 109	G1-CB1	P3	P3	P3	N/A	
TB 110	T-1, TB-1(*1)	WC-1	WC1	WC-1	WC-1	
TB 111	C1; CB-1	P-3	P-3	P-3	N/A	
TB 112	C1; CB-1	P-3	P-3	P-3	P-3	
TB 113	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
TB 114	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
TB 115	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
TB 116	NO FINISH	NO FINISH	NO FINISH	NO FINISH	NO FINISH	
ENT CUS	C1; CB-1	WC-1	WC-1	WC-1	WC-1	VESTIBUL/EXIT @ CUSTOMS. FINISHES ONLY BETWEEN RM TB101 & FS100

(*1) FLOOR BASE + TILE BASE SHALL BE PROVIDED "BY OTHERS" AND IS NOT A PART OF THIS CONTRACT. HOWEVER, FLOOR PREP FOR FLOOR TILE IS PART OF THIS CONTRACT IN PHASE 1A RENOVATION AREAS ONLY
NOTE: ALL HOLLOW MET. DOORS TO RECEIVE PAINT - P1; ALL HOLLOW MET. CASING TO RECEIVE P-2

ROOM FINISH SPECIFICATIONS

FLOORING

TZ-1 = TERAZZO -EPOXY RESIN (SEE SHEET I4.01 & SPECBBOOK FOR DETAILS)
TZ-2 = PRE-CAST DECO INSET-BROWN-SEE SPEC BOOK & SHEET I4.01 FOR DETAILS
TZ-3 = PRE-CAST DECO INSET-GREEN-SEE SPEC BOOK & SHEET I4.01 FOR DETAILS
T-1 = PORCELAIN TILE- SUPPLIED + INSTALLED BY OTHERS- SLAB PREP INCLUDED IN THIS CONTRACT FOR PHASE 1A AREAS
C-1 = 3 FRAME WILTON WOVEN CARPET (BY OTHERS NIC.) SLAB PREP INCLUDED IN THIS CONTRACT FOR PHASE 1A AREA
VCT = VINYL COMPOSITE TILE: ARMSTRONG, "EXCELON" COLOR DUTCH DELFT, OR APPROVED EQUAL

BASE

VB-1 = VINYL COVE BASE-4" - JOHNSONITE 4.00"X.125";COLOR: CHARCOAL OR APPROVED EQUAL
CB-1 = CARPET BASE IN/SURGED TOP-6" -BY OTHERS -(NIC)
TB-1 = PORCELAIN TILE BASE -BY OTHERS (NIC)
TZB-1 = 6" PRE CAST TERAZZO BASE - STRAIGHT. DETAILS IN SPEC BOOK

PAINT SHERWIN WILLIAMS OR APPROVED EQUAL

P-1 = LATEX ENAMEL - METAL PAINT @ HOLLOW METAL DOORS-(INTERIOR) = COLOR TBD. SATIN FINISH
P-2 = LATEX ENAMEL - METAL PAINT @ HOLLOW METAL DOOR CASINGS (INTERIOR) = COLOR TBD. SATIN FINISH
P-3 = LATEX ACRYLIC - SCRUBBABLE. SATIN FINISH. COLOR TBD
P-4 = LATEX ACRYLIC - SCRUBBABLE. SATIN FINISH. COLOR TBD
P-5 = LATEX ENAMEL METAL PAINT FOR HANDRAILS-COLOR TBD
P-6 = LATEX ACRYLIC - SCRUBBABLE - SEMIGLOSS COLOR TBD

WALL COVERING

WC-1 = 54"-TYPE II VINYL-BY OTHERS-GC TO SUPPLY FINISHED GYP BD. WALLS PREPPED& PRIMED TO A LEVEL 2 FINISH TO RECEIVE VINYL WALL COVERING

WALL TILE @ RESTROOMS:

T-1 = PORCELAIN TILE: CROSSVILLE EMPIRE 28"X14" VS77/P0, PARISIAN WHITE PO ,OR APPROVED EQUAL
T-2 = PORCELAIN TILE: CROSSVILLE EMPIRE 14"X14" VS77/P0, PARISIAN WHITE PO, OR APPROVED EQUAL
T-3 = PORCELAIN TILE: CROSSVILLE EMPIRE 7"X7" VS77/P0, PARISIAN WHITE PO, OR APPROVED EQUAL
T-4 = GLASSTILE: CROSSVILLE WATER CRYSTAL MOSAICS 1"X1" SUNSPRAY(BROWN),#WC220.101013 OR APPROVED EQUAL
T-5 = GLASSTILE: CROSSVILLE WATER CRYSTAL LISTELLO 7/8"X8" EBBTIDE, SEASPARAY(OLIVE) IRRIDESCENT #060, OR APPROVED EQUAL

Plotted by: Dx8230ua on 10/5/2007 12:36:03 PM

St. Petersburg Clearwater International Airport

THE LPA GROUP INCORPORATED
ENGINEERS ARCHITECTS PLANNERS
700 HUGER STREET
COLUMBIA, SOUTH CAROLINA 29201
POST OFFICE BOX 5805
COLUMBIA, SOUTH CAROLINA 29250-5805
Phone: 803/254-2211 Fax: 803/779-0482
DENNIS J. WIEHL FLORIDA ARCHITECT LICENSE # 11995
LPA GROUP INCORPORATED FLORIDA LICENSE# AA0003054

KTD Inc.
KELLY TAAFFE DESIGN
Lic# ID 0002289
FL# 13 0001146
Kelly@kellytaaffedesign.com
Tel.: 813.695.5049
Fax: 813.805.2371

TERMINAL IMPROVEMENT PROJECT PHASE 1

KEY PLAN



REVISIONS

No.	Description	Date	By

Designed by: | Drawn by: | Checked by:

Project Name:
TERMINAL IMPROVEMENT PROJECT PHASE 1

Drawing Name:
SPECIFICATIONS& SCHEDULES TICKETING B

LPA Project Number: AR178005.8
FAA AIP Project Number:
Date: AUGUST 31, 2007
Division :

Drawing Number:
I6.01